

**CET Building Glazing Replacement
Midlands Technical College, Northeast Campus
Columbia, South Carolina
OSE PROJECT No. H59-N366-SG
Studio 2LR No. 26006**

May 27, 2026

ADDENDUM NO. 2

This addendum forms a part of the Contract documents and modifies the original Bidding Documents and any previous Addenda as noted below. Acknowledge receipt of this Addendum in the space provided in the Bid Form. Failure to do so may subject Bidder to disqualification. The following items take precedence over reference portions of the specifications and drawings for the above-referenced project, and shall become a part thereof. Where any item called for in the documents is supplemented hereby, the original requirements shall remain in effect. All supplemental conditions shall be considered as added thereto. Where any original item is amended, voided or superseded, hereby, the provisions of such items not so specifically amended, voided or superseded shall remain in effect.

ATTACHMENTS:

None

MODIFICATIONS TO PROJECT MANUAL:

1. SECTION 088000 GLAZING
 - a. Delete paragraph 1.3, B, 2. Bird Friendly Glass is not required.

MODIFICATIONS TO DRAWINGS: None

REQUESTED PRODUCT APPROVALS: None

CLARIFICATIONS TO QUESTIONS FROM CONTRACTORS:

1. The original manufacturer of the glass and glazing system, Armarlite, is no longer in business. Installation of new curtainwall caps will require the replacement of the pressure bar.
2. The Standard Cap shown as 7/8", 1/2" will also be acceptable if that is the manufacturer's standard. All caps are to be replaced.
3. Where existing glazing is butt-glazed to adjacent metal panels, if the metal panels must be removed to replace the glazing, include removing and reinstalling when the new glazing is installed. As shown, clean all existing surfaces prior to completion.
4. Bidders may visit the site to look at the existing construction as they are able. Exploratory demolition prior to project award is not allowed.

END OF ADDENDUM NO. 2